BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/10/2017-18 Date: 12.06.2017

Indet No: BBMP/2017-18/OW/WORK_INDENT26235

SCHEDULE -B

Name of Work: Providing C.C Camera at Garbage Block Spots in ward no 16

Sl No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	4.55	Earthwork excavation by manulal means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / chapter 3 (Page no-142,item no19.1)2016-2017 PWD SR	Cum	237.00	Rupees Two Hundred Thirty Seven Only
2	0.33	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No. 4.3 of PWD SR 2016-17)	Cum	5365.00	Rupees Five Thousand Three Hundred Sixty Five Only
3	2.70	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No. 4.5 of PWD SR 2016-17)	Cum	6110.00	Rupees Six Thousand One Hundred Ten Only
4	20.00	2.0 Mega Pixel high definition upto 60 Mtr IR Night Vision CCTV Camera - EXIR with SD Card provision. (Approved Rate Sl.No. 1)	nos	10140.00	Rupees Ten Thousand One Hundred Forty Only
5	16.00	4.0 Mega Pixel high definition upto 60 Mtr IR Night Vision CCTV Camera - EXIR with SD Card provision. (Approved Rate Sl.No. 2)	nos	16897.00	Rupees Sixteen Thousand Eight Hundred Ninety Seven Only
6	13.00	Pole - Swg 20 Ft Height 100mm for PTZ erection with civil work, transportation. (Approved Rate Sl.No. 4)	nos	2600.00	Rupees Two Thousand Six Hundred Only

For Green Energy Technologies

Yashodha S.

Proprietrix

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner

7	3.00	16 Channel NVR (NVR Default without HDD) with 2SATA H264 compression. (Approved Rate Sl.No. 5)	nos	17108.00	Rupees Seventeen Thousand One Hundred Eight Only
8	6.00	2TB Harddisk (Surveillance). (Approved Rate Sl.No. 7)	nos	8008.00	Rupees Eight Thousand Eight Only
9	3.00	6 pin spike Pin . (Approved Rate Sl.No. 11)	nos	614.00	Rupees Six Hundred Fourteen Only
10	320.00	Outdoor supportable CAD6/CAD5 Cable / power cable FRLS . (Approved Rate Sl.No. 12)	mtr	146.00	Rupees One Hundred Forty Six Only
11	4.00	HDMI Patch Cable- for connectivity. (Approved Rate Sl.No. 14)	mtr	572.00	Rupees Five Hundred Seventy Two Only
12	2.00	6 U Rack with SS Lock & Key. (Approved Rate Sl.No. 16)	nos	5616.00	Rupees Five Thousand Six Hundred Sixteen Only
13	36.00	12V/2.5A Adopter. (Approved Rate Sl.No. 17)	nos	297.00	Rupees Two Hundred Ninety Seven Only
14	36.00	Junction Metal Box. (Approved Rate Sl.No. 20)	nos	468.00	Rupees Four Hundred Sixty Eight Only
15	36.00	Circuit Breaker for CCTV protection. (Approved Rate Sl.No. 21)	mtr	263.00	Rupees Two Hundred Sixty Three Only
16	36.00	3 pin socket. (Approved Rate Sl.No. 22)	nos	104.00	Rupees One Hundred Four Only
17	36.00	Hardware items and fixing charges. (Approved Rate Sl.No. 23)	nos	499.00	Rupees Four Hundred Ninety Nine Only
18	1.00	40" LED TV- Reputed make. (Approved Rate Sl.No. 24)	nos	46800.00	Rupees Forty Six Thousand Eight Hundred Only
19	1.00	UPS - 2 Hours Backup. (Approved Rate Sl.No. 25)	nos	9052.00	Rupees Nine Thousand Fifty Two Only
20	1.00	Battery - 2 Hours Backup. (Approved Rate Sl.No. 26)	nos	11207.00	Rupees Eleven Thousand Two Hundred Seven Only
21	1.00	5 Port Switch. (Approved Rate Sl.No. 27)	nos	598.00	Rupees Five Hundred Ninety Eight Only

For Green Energy Technologies

Yashodha S.
Proprietrix

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner

22	1.00	CPU - I3 Processor- 450MHz, 8GB RAM, 250GB Hard Disk Full Core. (Approved Rate Sl.No. 28)	nos	43227.00	Rupees Forty Three Thousand Two Hundred Twenty Seven Only
23	320.00	Outdoor supportable CAD6/CAD5 Cable - cabling, laying chargese. (Approved Rate Sl.No. 29)	mtr	146.00	Rupees One Hundred Forty Six Only
24	36.00	Installation charges for cameras and NVR (4-1). (Approved Rate Sl.No. 30)	mtr	3068.00	Rupees Three Thousand Sixty Eight Only
25	36.00	IP Configuration. (Approved Rate Sl.No. 31)	mtr	520.00	Rupees Five Hundred Twenty Only
26	36.00	Maintenance Uplink of CCTV Cameras. (Approved Rate Sl.No. 32)	mtr	151.00	Rupees One Hundred Fifty One Only

For Green Energy Technologies

Yashodha S

Yashodha S.
Proprietrix

Executive Engineer
RRNagara Division
BBMP

Signature of the contractor

Scanned by CamScanner